

Phase 2 will allow the operation to expand to include all of the lower pad; 5.1 acres. The receiving area and the upper access road including the turn-around will be completed and utilized in the expansion of phase 2. Deliveries of raw material will be relocated to the receiving area during the phase 2 expansion.

Phase 3 will be the final expansion of the facility to incorporate the upper pad; 2.79 acres. At the completion of the phase 3 expansion, the total area of the composting pads will be 7.9 acres.

A Phasing Plan is included in this report.

Sources and Descriptions of Compostable Material: Agri-Cycle will only accept compostable material by long term contract (Tipping Agreement) with approved "recyclers". A copy of the contract is included in the appendix. Prior to the execution of this contract, the recycler must provide samples and test results of their raw material for Agri-Cycle's approval. If the material is compatible with other raw material available to provide the proper carbon to nitrogen ratios required for the compost mix and the test results do not indicate contaminants that will impact either stormwater runoff or the quality of the finished compost, Agri-Cycle will agree to accept the material. A detailed schedule of deliveries will be negotiated to control both the coordination of deliveries and traffic as well as the quantities of raw material being delivered to provide compostable material in the correct proportions as required for the composting mix.

The facility will be operated in accordance with the NYS Conservation Laws, Subpart 360-5, Composting Facilities, Sections 360-5.1, 5.4 and 5.5. Agri-Cycle will only accept material that is approved and meets the requirements as stipulated by the Department of Environmental Conservation.

Hours of Operation: The hours of operation of the Agri-Cycle facility will be 9 am to 5 pm weekdays and 9 am to 12 am on Saturdays. The facility will be closed on all normally recognized Holidays. When the facility is closed, a chain with the word closed and the hours of operation will be drawn across the access road at a height of three feet and clearly marked for visibility. The Manager will arrive at the main office at 8:30 am. He will check the daily schedule of deliveries and shipments and finalize a work schedule for the day. Once the schedule is established, he will open the gate and the field office for business. At one half hour before closing time, the